

WEST BENGAL STATE ELECTRICITY DISTRIBUTION CO. LTD.
(A Government of West Bengal Enterprise)

STANDARD MEASUREMENT BOOK

PROJECT ID: wsedrftgyhu

1. Name of Work / Project:	sd5f6gt7yh8ujkiol dfghj
2. Scope / Particulars of Work:	Labour / erection work executed according to approved drawing for sd5f6gt7yh8ujkiol dfghj.
3. Reference Award / Project ID:	wsedrftgyhu
4. Reference Purchase Order (PO):	PO No. drftgyh Dated: 10-07-2026
5. Working Site / Location:	CHANCHAL DIVISION, CHANCHAL, WBSEDCL
6. Name of Contractor / Agency:	SA CONSTRUCTION (ELECTRICAL ERECTION AND CONTRACTS)
7. Contractor Vendor ID / Code:	701254
8. Date of Commencement of Work:	27-07-2026
9. Date of Completion of Work:	26-07-2026
10. Date of Site Measurement:	31-07-2026
11. Measurement Recorded By:	Sub-Assistant Engineer

AGENCY ACCEPTING MEASUREMENT

Signature of Contractor / Agency

RECORDED & MEASURED BY

Sub-Assistant Engineer (SAE)

CHECKED & CERTIFIED BY

Assistant Engineer (AE) / SM

** ORIGINAL FOR RECIPIENT **

SA CONSTRUCTION

Address: MAHANANDPUR, TULSHIHATA, HARISHCHANDRAPUR
GSTIN: 23423423G4H234234H234

TAX INVOICE

BILL TO: DIVISIONAL MANAGER CHANCHAL DIVISION, CHANCHAL, WBSEDCL GSTIN: 2352G3Y4U2G423234	Invoice No: SA/26-27/KSD/02 Invoice Date: 27-07-2026 Project ID: wsedrftgyhu PO Number: drftgyh PO Date: 10-07-2026
---	--

Project Subject:	Labour / erection work executed according to approved drawing for sd5f6gt7yh8ujkiol dfghj.
-------------------------	--

SI	Labour Erection Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Fixing of 1Ph Service Connection (without cable)	1.000	NOS	1,578.00	1,578.00
2	Erection of 8MTR PCC Pole (LT) Without Painted	1.000	NOS	1,501.00	1,501.00
3	Pole GIS Survey	1.000	NOS	31.00	31.00
4	Earthing Complete	1.000	NOS	313.00	313.00
5	LT Stay Set Complete Labour	2.000	SET	555.00	1,110.00
6	Erection of Distribution Box LT ABC	3.000	NOS	507.00	1,521.00
7	Fixing of IPC Connector LT ABC	12.000	NOS	75.00	900.00
8	Erection of Anchor/Dead End Clamp LT ABC	2.000	NOS	154.00	308.00
9	Erection of Suspension Clamp LT ABC	1.000	NOS	154.00	154.00
10	Survey for L.T.O.H Line	0.080	KM	1,714.00	137.12
11	Stringing & Sagging LT AB Cable 3CX70+1CX16+1CX50	0.080	KM	50,000.00	4,000.00
TOTAL LABOUR COST (A)					Rs. 11,553.12
Add: CGST @ 9% on Labour charges					Rs. 1,039.78
Add: SGST @ 9% on Labour charges					Rs. 1,039.78
GRAND TOTAL (BILLED LABOR VALUE)					Rs. 13,632.68

Amount in Words: Rupees Thirteen Thousand Six Hundred Thirty Two and Sixty Eight Paise Only

Declaration: We declare that this invoice shows the actual price of the goods/services described and that all particulars are true and correct.

Authorized Signature

** DUPLICATE FOR PROVIDER **

SA CONSTRUCTION

Address: MAHANANDPUR, TULSHIHATA, HARISHCHANDRAPUR
GSTIN: 23423423G4H234234H234

TAX INVOICE

BILL TO: DIVISIONAL MANAGER CHANCHAL DIVISION, CHANCHAL, WBSEDCL GSTIN: 2352G3Y4U2G423234	Invoice No: SA/26-27/KSD/02 Invoice Date: 27-07-2026 Project ID: wsedrftgyhu PO Number: drftgyh PO Date: 10-07-2026
---	--

Project Subject:	Labour / erection work executed according to approved drawing for sd5f6gt7yh8ujkiol dfghj.
-------------------------	--

SI	Labour Erection Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Fixing of 1Ph Service Connection (without cable)	1.000	NOS	1,578.00	1,578.00
2	Erection of 8MTR PCC Pole (LT) Without Painted	1.000	NOS	1,501.00	1,501.00
3	Pole GIS Survey	1.000	NOS	31.00	31.00
4	Earthing Complete	1.000	NOS	313.00	313.00
5	LT Stay Set Complete Labour	2.000	SET	555.00	1,110.00
6	Erection of Distribution Box LT ABC	3.000	NOS	507.00	1,521.00
7	Fixing of IPC Connector LT ABC	12.000	NOS	75.00	900.00
8	Erection of Anchor/Dead End Clamp LT ABC	2.000	NOS	154.00	308.00
9	Erection of Suspension Clamp LT ABC	1.000	NOS	154.00	154.00
10	Survey for L.T.O.H Line	0.080	KM	1,714.00	137.12
11	Stringing & Sagging LT AB Cable 3CX70+1CX16+1CX50	0.080	KM	50,000.00	4,000.00
TOTAL LABOUR COST (A)					Rs. 11,553.12
Add: CGST @ 9% on Labour charges					Rs. 1,039.78
Add: SGST @ 9% on Labour charges					Rs. 1,039.78
GRAND TOTAL (BILLED LABOR VALUE)					Rs. 13,632.68

Amount in Words: Rupees Thirteen Thousand Six Hundred Thirty Two and Sixty Eight Paise Only

Declaration: We declare that this invoice shows the actual price of the goods/services described and that all particulars are true and correct.

Authorized Signature

SA CONSTRUCTION

Address: MAHANANDPUR, TULSHIHATA, HARISHCHANDRAPUR
GSTIN: 23423423G4H234234H234

TAX INVOICE

BILL TO: DIVISIONAL MANAGER CHANCHAL DIVISION, CHANCHAL, WBSEDCL GSTIN: 2352G3Y4U2G423234	Invoice No: SA/26-27/KSD/02 Invoice Date: 27-07-2026 Project ID: wsedrftgyhu PO Number: drftgyh PO Date: 10-07-2026
---	--

Project Subject: Labour / erection work executed according to approved drawing for sd5f6gt7yh8ujkiol dfghj.
--

SI	Labour Erection Description	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Fixing of 1Ph Service Connection (without cable)	1.000	NOS	1,578.00	1,578.00
2	Erection of 8MTR PCC Pole (LT) Without Painted	1.000	NOS	1,501.00	1,501.00
3	Pole GIS Survey	1.000	NOS	31.00	31.00
4	Earthing Complete	1.000	NOS	313.00	313.00
5	LT Stay Set Complete Labour	2.000	SET	555.00	1,110.00
6	Erection of Distribution Box LT ABC	3.000	NOS	507.00	1,521.00
7	Fixing of IPC Connector LT ABC	12.000	NOS	75.00	900.00
8	Erection of Anchor/Dead End Clamp LT ABC	2.000	NOS	154.00	308.00
9	Erection of Suspension Clamp LT ABC	1.000	NOS	154.00	154.00
10	Survey for L.T.O.H Line	0.080	KM	1,714.00	137.12
11	Stringing & Sagging LT AB Cable 3CX70+1CX16+1CX50	0.080	KM	50,000.00	4,000.00
TOTAL LABOUR COST (A)					Rs. 11,553.12
Add: CGST @ 9% on Labour charges					Rs. 1,039.78
Add: SGST @ 9% on Labour charges					Rs. 1,039.78
GRAND TOTAL (BILLED LABOR VALUE)					Rs. 13,632.68

Amount in Words: Rupees Thirteen Thousand Six Hundred Thirty Two and Sixty Eight Paise Only

Declaration: We declare that this invoice shows the actual price of the goods/services described and that all particulars are true and correct.

Authorized Signature

ABSTRACT OF LABOR ERECTION BILL (VALUATION & RECORD OF QUANTITIES)

PO No: drftgyh | Date: 10-07-2026 | Project ID: wsedrftgyhu | Measurement Date: 31-07-2026

SI	Labour Erection Description	Quantity			Unit	Rate (Rs)	Actual Rate	Amount		
		This Bill (A)	Prior (b)	Upto (c=a+b)				This Bill (d)	Prior (e)	Upto (f=d+e)
1	Fixing of 1Ph Service Connection (without cable)	1.000	0.000	1.000	NOS	1,578.00	1,578.00	1,578.00	0.00	1,578.00
2	Erection of 8MTR PCC Pole (LT) Without Painted	1.000	0.000	1.000	NOS	1,501.00	1,501.00	1,501.00	0.00	1,501.00
3	Pole GIS Survey	1.000	0.000	1.000	NOS	31.00	31.00	31.00	0.00	31.00
4	Earthing Complete	1.000	0.000	1.000	NOS	313.00	313.00	313.00	0.00	313.00
5	LT Stay Set Complete Labour	2.000	0.000	2.000	SET	555.00	555.00	1,110.00	0.00	1,110.00
6	Erection of Distribution Box LT ABC	3.000	0.000	3.000	NOS	507.00	507.00	1,521.00	0.00	1,521.00
7	Fixing of IPC Connector LT ABC	12.000	0.000	12.000	NOS	75.00	75.00	900.00	0.00	900.00
8	Erection of Anchor/Dead End Clamp LT ABC	2.000	0.000	2.000	NOS	154.00	154.00	308.00	0.00	308.00
9	Erection of Suspension Clamp LT ABC	1.000	0.000	1.000	NOS	154.00	154.00	154.00	0.00	154.00
10	Survey for L.T.O.H Line	0.080	0.000	0.080	KM	1,714.00	1,714.00	137.12	0.00	137.12
11	Stringing & Sagging LT AB Cable 3CX70+1CX16+1CX50	0.080	0.000	0.080	KM	50,000.00	50,000.00	4,000.00	0.00	4,000.00
TOTAL LABOR ERECTION COST (A)								11,553.12	0.00	11,553.12
Add: CGST @ 9% on Labor charges								1,039.78	0.00	1,039.78
Add: SGST @ 9% on Labor charges								1,039.78	0.00	1,039.78
GRAND TOTAL (BILLED LABOR VALUE)								13,632.68	0.00	13,632.68

AGENCY ACCEPTING MEASUREMENT

Signature of Contractor / Agency

MATERIAL CONSUMPTION & COMPLETION REPORT

PO No: drftgyh | Date: 10-07-2026 | Project ID: wsedrftgyhu

SI	Item Code	Material Description	Unit	Est Qty	Act Qty	Deviation
1	0110030141	PCC POLE: 8M LONG	NOS	3.000	1.000	-2.000
2	0504110541	G I EARTH SPIKE 1853X20MM	NOS	3.000	1.000	-2.000
3	0503010811	G.I. WIRE 5 MM	MT	0.009	0.003	-0.006
4	0504130332	GI STAY SET LT(1680X16MM)WRKG LD-5100KG	SET	2.000	2.000	0.000
5	0503050611	G.I. STAY WIRE 7/ 2.5MM (12 SWG)	MT	0.008	0.008	0.000
6	0508040741	PORCELAIN GUY INSULATOR LT	NOS	2.000	2.000	0.000
7	0504060941	LTDISTBOX 3PH CON.WH ST.STRAP&BUCKLE-ABC	NOS	3.000	3.000	0.000
8	0504027141	INSULATION-PIERCING CONNECTOR -ABC TO ABC TEE JOINT	NOS	12.000	12.000	0.000
9	0505034141	DEAD END CLAMP-LT ABC(3X70+1X16+1X50SMM)	NOS	2.000	2.000	0.000
10	0505030841	EYE HOOK FOR ANCHOR & SUSPN. CLAMP	NOS	3.000	3.000	0.000
11	0505030641	SUSPENTION CLAMP WITH BRKT 35SQMM MESENGER	NOS	1.000	1.000	0.000
12	0103011511	M.S FLAT 65X6 MM	MT	0.003	0.003	0.000
13	0501030521	CABLE (LT AERIAL BUNCHED 1.1 KV) 3C X 70+1C X 16+ 1C X 50SQMM	KM	0.080	0.080	0.000

Verified that materials issued by office have been consumed at site as per actuals.

Contractor Signature

Site Engineer Signature

DETAILED MEASUREMENT SHEET (MATERIALS)

PO No: drftgyh | Project ID: wsedrftgyhu

SI	Material Description	No	L	B	D/H	PO Qty	Measured Qty	Unit
1	PCC POLE: 8M LONG	1	1.00	1.00	1.00	3.000	1.000	NOS
2	G I EARTH SPIKE 1853X20MM	1	1.00	1.00	1.00	3.000	1.000	NOS
3	G.I. WIRE 5 MM	1	1.00	1.00	1.00	0.009	0.003	MT
4	GI STAY SET LT(1680X16MM)WRKG LD-5100KG	1	1.00	1.00	1.00	2.000	2.000	SET
5	G.I. STAY WIRE 7/ 2.5MM (12 SWG)	1	1.00	1.00	1.00	0.008	0.008	MT
6	PORCELAIN GUY INSULATOR LT	1	1.00	1.00	1.00	2.000	2.000	NOS
7	LTDISTBOX 3PH CON.WH ST.STRAP&BUCKLE-ABC	1	1.00	1.00	1.00	3.000	3.000	NOS
8	INSULATION-PIERCING CONNECTOR -ABC TO ABC TEE JOINT	1	1.00	1.00	1.00	12.000	12.000	NOS
9	DEAD END CLAMP-LT ABC(3X70+1X16+1X50SMM)	1	1.00	1.00	1.00	2.000	2.000	NOS
10	EYE HOOK FOR ANCHOR & SUSPN. CLAMP	1	1.00	1.00	1.00	3.000	3.000	NOS
11	SUSPENTION CLAMP WITH BRKT 35SQMM MESENGER	1	1.00	1.00	1.00	1.000	1.000	NOS
12	M.S FLAT 65X6 MM	1	1.00	1.00	1.00	0.003	0.003	MT
13	CABLE (LT AERIAL BUNCHED 1.1 KV) 3C X 70+1C X 16+ 1C X 50SQMM	1	1.00	1.00	1.00	0.080	0.080	KM

Signature of Contractor / Agency
M/S: SA CONSTRUCTION

Verified & Certified By:
Measurement Taken By: Sub-Assistant Engineer
Certified By: Assistant Engineer

DETAILED MEASUREMENT & ERECTION SHEET (LABOR)

PO No: drftgyh | Project ID: wsedrftgyhu

SI	Labour Work Description	No	L	B	D/H	PO Qty	Measured Qty	Unit
1	Fixing of 1Ph Service Connection (without cable)	1	1.00	1.00	1.00	1.000	1.000	NOS
2	Erection of 8MTR PCC Pole (LT) Without Painted	1	1.00	1.00	1.00	3.000	1.000	NOS
3	Pole GIS Survey	1	1.00	1.00	1.00	3.000	1.000	NOS
4	Earthing Complete	1	1.00	1.00	1.00	3.000	1.000	NOS
5	LT Stay Set Complete Labour	1	1.00	1.00	1.00	2.000	2.000	SET
6	Erection of Distribution Box LT ABC	1	1.00	1.00	1.00	3.000	3.000	NOS
7	Fixing of IPC Connector LT ABC	1	1.00	1.00	1.00	12.000	12.000	NOS
8	Erection of Anchor/Dead End Clamp LT ABC	1	1.00	1.00	1.00	2.000	2.000	NOS
9	Erection of Suspension Clamp LT ABC	1	1.00	1.00	1.00	1.000	1.000	NOS
10	Survey for L.T.O.H Line	1	1.00	1.00	1.00	0.080	0.080	KM
11	Stringing & Sagging LT AB Cable 3CX70+1CX16+1CX50	1	1.00	1.00	1.00	0.080	0.080	KM

Signature of Contractor / Agency
M/S: SA CONSTRUCTION

Verified & Certified By:
Measurement Taken By: Sub-Assistant Engineer
Certified By: Assistant Engineer

SA CONSTRUCTION

Address: MAHANANDPUR, TULSHIHATA, HARISHCHANDRAPUR
GSTIN: 23423423G4H234234H234

PROJECT COMPLETION & COMPLIANCE CERTIFICATE

Project ID: wsdrtgyhu
PO Number: drftgyh
Commencement: 27-07-2026

Billing Date: 27-07-2026
PO Date: 10-07-2026
Completion: 26-07-2026

This is to certify that the contract work of 'sd5f6gt7yh8ujkiol dfghj' awarded to us vide the above-mentioned Purchase Order has been executed successfully. In connection with the work completed and the billing thereof, we hereby declare and certify that:

1. The work has been executed in all respects as per the rules, department guidelines, approved drawings, and technical specifications.
2. The execution of the work has been completed within the stipulated timeframe without delay.
3. The bill claimed for this work has not been claimed/submitted before. This is the first and final bill for the executed work.
4. The claimed quantities are accurate as per actual execution on site and have been verified and measured by the department.
5. The payment against the billed erection charges may kindly be released in favour of the agency (M/S SA CONSTRUCTION).
6. All materials issued by the division have been fully and properly utilised in the work as per the Material Reconciliation statement.
7. All items and quantities claimed in the bill are strictly as per actual site installations and measurements.
8. The work was executed under the direction and supervision of the department's Site Engineer.
9. No departmental store materials have been wasted, lost, or unaccounted for during execution of the contract.
10. We accept full responsibility for the stability, safety, and quality of work executed at the site.

Signature of Contractor / Agency
M/S: SA CONSTRUCTION

PROJECT ESTIMATE & BILL OF QUANTITIES

Project ID: wsdrftgyhu | PO No: drftgyh

SI	Item Description	Type	Unit	Rate (Rs)	Quantity	Amount (Rs)
A. MATERIALS						
1	PCC POLE: 8M LONG	Material	NOS	5,293.69	1.000	5,293.69
2	G I EARTH SPIKE 1853X20MM	Material	NOS	465.88	1.000	465.88
3	G.I. WIRE 5 MM	Material	MT	80,107.31	0.003	240.32
4	GI STAY SET LT(1680X16MM)WRKG LD-5100KG	Material	SET	580.51	2.000	1,161.02
5	G.I. STAY WIRE 7/ 2.5MM (12 SWG)	Material	MT	86,748.14	0.008	693.99
6	PORCELAIN GUY INSULATOR LT	Material	NOS	17.64	2.000	35.28
7	LTDISTBOX 3PH CON.WH ST.STRAP&BUCKLE-ABC	Material	NOS	1,499.51	3.000	4,498.53
8	INSULATION-PIERCING CONNECTOR -ABC TO ABC TEE JOINT	Material	NOS	114.95	12.000	1,379.40
9	DEAD END CLAMP-LT ABC(3X70+1X16+1X50SMM)	Material	NOS	340.09	2.000	680.18
10	EYE HOOK FOR ANCHOR & SUSPN. CLAMP	Material	NOS	92.38	3.000	277.14
11	SUSPENTION CLAMP WITH BRKT 35SQMM MESENGER	Material	NOS	367.41	1.000	367.41
12	M.S FLAT 65X6 MM	Material	MT	105,704.06	0.003	317.11
13	CABLE (LT AERIAL BUNCHED 1.1 KV) 3C X 70+1C X 16+ 1C X 50...	Material	KM	275,958.51	0.080	22,076.68
Material Base Total						37,486.63
Add: Sundries @ 5%						1,874.33
TOTAL MATERIAL COST (A)						39,360.96
B. ERECTION / LABOR						
1	Fixing of 1Ph Service Connection (without cable)	Labor	NOS	1,578.00	1.000	1,578.00
2	Erection of 8MTR PCC Pole (LT) Without Painted	Labor	NOS	1,501.00	1.000	1,501.00
3	Pole GIS Survey	Labor	NOS	31.00	1.000	31.00
4	Earthing Complete	Labor	NOS	313.00	1.000	313.00
5	LT Stay Set Complete Labour	Labor	SET	555.00	2.000	1,110.00
6	Erection of Distribution Box LT ABC	Labor	NOS	507.00	3.000	1,521.00
7	Fixing of IPC Connector LT ABC	Labor	NOS	75.00	12.000	900.00
8	Erection of Anchor/Dead End Clamp LT ABC	Labor	NOS	154.00	2.000	308.00
9	Erection of Suspension Clamp LT ABC	Labor	NOS	154.00	1.000	154.00
10	Survey for L.T.O.H Line	Labor	KM	1,714.00	0.080	137.12
11	Stringing & Sagging LT AB Cable 3CX70+1CX16+1CX50	Labor	KM	50,000.00	0.080	4,000.00
TOTAL LABOR COST (B)						11,553.12
C. OVERHEADS & TAXES						
Supervision @ 10% on (A+B)						5,091.41
GST @ 18% on Labour only						2,079.56
Sub-Total						58,085.05
Add: Cess @ 1% on (Mat+Lab+Sup)						560.05
GRAND TOTAL						58,645.11